

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20076-00-00
Spot: CNWSE Sec/Twnshp/Rge: 36-4S-37W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: BEVERLEY SCOTT Well Number: 1
County: CHEYENNE Total Vertical Depth: 4765 feet

Operator License No.: 4273 Conductor Pipe: Size feet: \$154.86
Op Name: H & R EXPLORATION & PRODUCTION, I Surface Casing: Size 8.625 feet: 343 w/280 sxs cmt
Address: 1113 SOUTH 10TH AVENUE PO BOX 101 Production: Size 4.5 feet: 4760 w/250 sxs cmt
SIDNEY, NE 69162 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/15/2002 9:00 AM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 460 cu.ft. cement slurry.
Order one permanent plug.
Order 4 sxs common cement.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/15/2002 11:00 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 343' w/280 sxs cwc. 4 1/2" set at 4760' w/250 sxs.
Prod. Perfs 4693' - 4717'. OA.
Exempt area. PBTD 4760'.
Fluid level near TD. Depleted production zone.
Set permanent plug at 4640' with 4 sxs common cement on plug with bailer.
Shot off and recovered 2000' of casing.
Filled hole with 460 cu.ft. of cement slurry.
Plug complete.

RECEIVED
JAN 31 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE Feb 1-02

INV. NO. 2002061328

JAN 23 2002

SHAKESPEARE OIL CO., INC.
P.O. BOX 669

#1 BEVERLEY SCOTT

36-4-37W
C NW SE

SALEM, ILL. 62881

CONTR MURFIN DRLG. CO.

CTY CHEYENNE

GEOL _____ FIELD LITTLE BEAVER CREEK EXT.

E 3377 KB CM 10/2/78 CARD ISSUED 11/23/78 P 108 BOPD

CHER LM 4693-4717
OA

+	+	+
+	+	+
+	+	+

API 15-023-20,076

LOG	TOPS	DEPTH	DATUM
NIOB		1182	+2195
FT HAYS		1600	+1777
ANH		3108	+ 269
B ANH		3146	+ 231
HEEB		4112	- 735
LANS		4260	- 883
J		4441	-1064
B KC		4550	-1173
MARM		4632	-1255
CHER SH		4684	-1307
U CHER LS		4690	-1313
LTD		4725	-1348
RTD		4765	-1388

8-5/8" 343/280 SX; 4-1/2" 4760/250 SX
DST (1) 4430-61/30-30-30-30, 75' M,
SIP 79-95#, FP 79-79#
DST (2) 4678-4725, (CHER)/30-30-30-45,
500' GIP, 670' CGO, 180' MGO, SIP
1303-1303#, FP 63-237#, 237-356#
MICT - CO, PF 4713-17, SWB 5 BOPH, PF
4693-4703, SD/ON, FU 2500' FL, SWB 7
BOPH/1 HR, SWB 7 BOPH/1 HR & 3 BOPH
LAST HOUR OF 7 HR TEST, AC 3000, REC
LD, SWB 81 BO, 5 HRS, SD/ON, FU 3000' FL
SWB 58 BO/5 HRS, T&R, POP, P 108 BOPD

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS