

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20067-00-00
Spot: CSWNE Sec/Twnshp/Rge: 36-4S-37W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: ROSIE REUBER Well Number: 1
County: CHEYENNE Total Vertical Depth: 4752 feet

Operator License No.: 4273 Conductor Pipe: Size feet: \$154.44
Op Name: H & R EXPLORATION & PRODUCTION, I Surface Casing: Size 8.625 feet: 368 w/280 sxs cmt
Address: 1113 SOUTH 10TH AVENUE PO BOX 101 Production: Size 4.5 feet: 4723 w/250 sxs cmt
SIDNEY, NE 69162 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/14/2002 1:00 PM
Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.
Proposal Rcvd. from: RANDY Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 460 cu.ft. cement slurry.
Order permanent plug.
Order 4 sxs common cement.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/14/2002 3:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 368' w/280 sxs cwc. 4 1/2" set at 4723' w/250 sxs.
Prod.Perfs 4444' - 4450' and 4640' - 4645'.
Exempt area. PBTD 4723'.
Fluid level near TD. Depleted production zone.
Set permanent plug at 4390' with 4 sxs common cement on plug with bailer.
Shot off and recovered 2000' of casing.
Filled hole with 460 cu.ft. of cement slurry.
Plug complete.

RECEIVED
JAN 31 2002
KCC WICHITA

Remarks:

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE Feb 1, 02

INV. NO. 2002061328

JAN 23 2002

SHAKESPEARE OIL CO., INC.
 BOX 669, SALEM, ILL. 62881

#1 ROSIE REUBER

36-4-37W
 C SW NE

CONTR MURFIN DRILLING CO.

CTY CHEYENNE

GEOL DARRELL ROBERTS

FIELD WC (1 1/4 NW OF LITTLE BEAVER

E 3381 KB CM 6/8/78 CARD ISSUED 8/3/78 IP 138 BOPD + TR WTR

CREEK SE)

LKC 4444-50 &
 MARM 4640-45 (NEW PAY)

+	+	+
+	+	+
+	+	+

API 15-023-20,067

LOG	TOPS	DEPTH	DATUM
OREAD	4194	- 813	
HEEB	4214	- 833	
LANS	4262	- 881	
J ZN	4444-52	-1063	
BKC	4556	-1175	
MARM	4640-46	-1259	
RTD	4742	-1361	
LTD	4752	-1371	

8-5/8" 368/280sx, 4 1/2" 4723/250sx
 DST (1) 4340-79/30-45-30-45, 890' SW,
 SIP 1241-1187#, FP 27-309#, 336-
 436#
 DST (2) 4430-50/45-45-45-45, 516' CO,
 279' SMCO, SIP 1178-1124#, FP 36-
 200#, 227-290#
 DST (3) 4624-40/45-45-45-45, 540' GIP,
 75' CO, 10' HCOM, SIP 1271-1253#,
 FP 17-35#, 26-44#
 MICT-PF 15/4640-45, AC 500, SWB LD,
 AC 2500, REC LD, FU 1800' GAS, 200' OIL
 & 150' AC WTR, SWB 2BOPH, BP @ 4540',
 PF 18/4444-50, AC 500, SWB 5BOPH, NW,
 AC 8000, PULLED PLUG, CO TD, P 26
 BO/7HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS