

KANSAS

Form CP-3
Rev. 6-9-67



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1967

10-23-1967

CONSERVATION DIVISION
Wichita, Kansas

15-039-20025-00-00

Operator's Full Name C & G Drilling Company,

Complete Address 107 Rule Building, Wichita, Kansas.

Lease Name Bishop Well No. 1

Location NE-SE-SW Sec. 8 Twp. 4 Rge. (E) (W) 28

County Decatur Total Depth 4160

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:30PM Day 19 Month 10 Year 1967

The above well was plugged as follows:

243'--8 5/8" Surface casing, cement circulated with 200 Sx.
Dakota section from 1600' to 1460'.

Circulated hole with heavy mud. Pulled DP to 1620' and displaced 100 Sx. cement
from 1620' to 1300'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 10/23/67

INV. NO. 6549-W