

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-039-20080-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Thunderbird Drilling, Incorporated.

Complete Address: 400 North Woodlawn, Wichita, Kansas.

Lease Name Pawlicek Well No. 1

Location NW-NW-SW Sec. 2 Twp. 4 Rge. (E) (W) 28

County Decatur Total Depth 3975'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drilling Company, Incorporated.

Address: 500 Bitting Building, Wichita, Kansas. License No. _____

Operation Completed: Hour 8:45 AM Day 18 Month 3 Year 1969

The Above well was plugged as follows:

252'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1400'.

Circulated hole with heavy mud. Pulled DP to 1620' and displaced 100 Sx. cement thru
DP from 1620' to 1295'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 3/20/69
INV. NO. 9484-W