

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -029 - 20,006 -0000 (of this well)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 04 1976  
5-4-76  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Anadarko Production Co. Diamond Shamrock Corp.

Complete Address Box 351, Liberal, Kansas 67901

Lease Name Lambert "A" Well No. 1

Location C NE SW Sec. 22 Twp. 5 Rge. 1 (E) (W) X

County Cloud Total Depth 3046'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor B & N Drilling Co. and Sun Cementing Co.

Address 305 Professional Bldg., Independence, Ks. License No.       

Operation Completed: Hour 2 PM Day 22 Month April Year 1976

The above well was plugged as follows:

Hole filled with mud. Plug pushed to 500' and 40 sacks cement pumped through drill pipe at 500'. 25 sacks cement pumped through drill pipe at 275'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole bridged and cemented with 2 sacks cement. Mousehole bridged and cemented with 2 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5-04-76

INV. NO. 3156-W