

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 22 1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-183-20003-00-00

2-22-72

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Ehrlich Drilling Company & Claud Exploration

Complete Address 231 W. 20th., Concordia, Kansas

Lease Name W. E. Oliver Well No. # 1

Location N/2 NE SW Sec. 5 Twp. 5 Rge. 11 (E) (W) W

County Smith Total Depth 4190

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Ehrlich Drilling Company

Address Wilson, Kansas License No.     

Operation Completed: Hour 2 A.M. Day 17 Month 2 Year 1972

The above well was plugged as follows:

8 5/8" csg. 237' Cwc.

Circulated hole with heavy mud to 600', set plug, & displaced 50 sax cement thru

drill pipe. Mud to 220', displaced 25 sax cement thru drill pipe. Mud to 40',

1/2 sax hulls, plug, & displaced 10 sax cement with Allied Cementing Company's

pump truck, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/28/72  
INV. NO. 5222-W

Signed: [Signature]  
Well Plugging Supervisor