

B

DISTRICT CONSERVATION AGENT'S REPORT

15-089-00001-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. CSL nw
LOCATION GS-NW/4
SEC. 10 TWP. 5 RGE. 10W

Dry Hole *** Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Beard

Operator Louis M. Mai. Address Russell, Kansas.

Field _____ County Jewell

Total Depth 2715' Feet.

(Describe briefly the manner in which the well was plugged)

Plugging Contractor.- Louis M. Mai.

Plugging Contractor's License No.- _____

Address.- Russell, Kansas.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1956
9-17-56
CONSERVATION DIVISION
WICHITA, KANSAS

Surface pipe - None. 8 5/8" @ 2540' , 10" @ 815' , 12 1/8" @ 590'
and 15 1/8" @ 370'. Started 8 5/8" pipe, when free, stopped and filled hole
with heavy mud. (Had Halliburton Pump Truck to jet up pond to get heavy
mud and pump into the hole). After 8 5/8" pipe was out, the same
procedure with the 10" & 12 1/8" pipe. Then with the 15 1/8" pipe, we pulled
it up to 270' from top, set plug, rock bridge and pumped in 60 sx. cem.
for fresh water plug. Pulled 15 1/8" pipe out and mud to 35' from top, set
plug, rock bridge and 20 sx. cem.
to base of cellar.

Milton Schubert
District Conservation Agent

Date Sept 14, 1956

(Halliburton was used for mud & cem.)

PLUGGING
FILE SEC. 10 T. S R. 10W
BOOK PAGE 99 LINE 31