

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-147-20301-00-00

API Number 15- -

245 North Water
Wichita, KS 67202

Operator's Full Name PETROLEUM MANAGEMENT, INC

Complete Address 400 N. WOODLAWN - SUITE 201 - WICHITA, MO. 67208

Lease Name DE-BEY Well No. #1

Location NW-NW-NE Sec. 21 Twp. 5 Rge. 17 (East) (West)

County PHILLIPS Total Depth 3360 ^{ft}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor HELSO CASING PULLING (MILLARD HELSO)

Address BOX 176 CHASE, MANS License No. 683

Operation Completed: Hour: 4:00 PM Day: 3RD Month: FEB Year: 1981

The above well was plugged as follows:

8 5/8" 226 ^{ft} SO. CUL 1/125 ^{ft} CMT. → 4 1/2" SET @ 3259 ^{ft}

PERF'S 2881 ^{ft} TOP. → SAND BOTTOM TO 2800 ^{ft} AND 1/4 ^{ft} CMT.

SHOT PIPE SEVERAL TIMES - RECOVERED 2566 ^{ft}

ORDERED 140 ^{ft} 50/50 Pozmix 6% GEL. - 23 ^{ft} GEL - 5 ^{ft} HULL'S + 8 3/8" PLUG.

PUMPED IN 8 3/8" WITH PUMP TRUCK.

PUT IN 4 ^{ft} HULL'S - 18 ^{ft} GEL. → 70 ^{ft} CMT. → 5 ^{ft} GEL. → 1 ^{ft} HULL'S

RELEASED PLUG. AND 70 ^{ft} CMT. - MAX PRESSURE 200 ^{lbs}

CEMENTED BY HALLIBURTON CMT.

COMMISSION
2-6-81
FEB - 6 1981

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/6/81

INV. NO. 7812

Signed: [Signature]
Conservation Division Agent

CONSERVATION DIVISION
Wichita, Kansas