



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-147-20192-00-00

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUN 5 1975
6-5-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas

Lease Name Fulghum Well No. I

Location SW SW SW Sec. 20 Twp. 5 Rge. (E) (W) 17

County Phillips Total Depth 3330'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 8 A Day 2 Month 6 Year 1975

The above well was plugged as follows:

RTD 3330' 8 5/8 csg 208' cwc 140 sk. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 660' thru drill pipe.

Heavy mud to 185' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Les E. Massey
Well Plugging Supervisor

INVOICED

DATE 6/9/75

INV. NO. 1461-W