

15-089-01012-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Harry Mann Address 1017 Campbell, Beloit, Kansas
(Applicant)

Lease (Farm Name) Beard Well No. 1

well Location NE SW SW Sec. 10 Twp. 5S Rge. 10W (X)-(W)

County Jewell Field Name (if any) Wildcat

Total Depth 4052 Oil Gas Dry Hole X

Was well log filed with application? Yes . If not, explain:

Date and hour plugging is desired to begin November 23, 1952

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully and exceptions desired, NO EXCEPTIONS

(Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner

J. A. Melland Address 1111 North Main, Hutchinson, Kans.

Name of Plugging Contractor J. A. Melland

Address 1111 North Main, Hutchinson, Kansas

Invoice covering assessment for plugging this well should be sent to

Plugging Fee paid by J. A. Melland Address Hutchinson, Kansas.

and payment will be guaranteed by applicant.

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1953

CONSERVATION DIVISION
Wichita, Kansas

3-13-53

J. A. Melland
Applicant or Acting Agent

Date March 13, 1953

PLUGGING

FILE SEC 10 T 5 R 1024

BOOK PAGE 62 LINE 16

15-089-01012-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

File One Copy

Lease Owner Harry Mann, et al Address Beliot, Kansas
(Applicant)

Lease (Farm Name) Beard Well No. 1

well Location Gen. S/2 SW/4 Sec. 10 Twp. 5S Rge. (E)-(W) 10

County Jewell Field Name (if any) _____

Total Depth 4052' Oil ___ Gas ___ Dry Hole X

Was well log filed with application? Yes . If not, explain: _____

Date and hour plugging is desired to begin 1:00 p.m. November 23, 1952

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully and exceptions desired, _____

(Use an additional sheet if necessary) _____

Name of the person on the lease in charge of well for owner _____

Harry Mann Address Beliot, Kansas

Name of Plugging Contractor J. A. Melland, Drilling Contractor

Address 1111 North Main Street, Hutchinson, Kansas

Invoice covering assessment for plugging this well should be sent to _____

Harry Mann Address 1017 North Campbell, Beliot, Kans.

and payment will be guaranteed by applicant.

STATE CORPORATION COMMISSION

MAR 2 1953

CONSERVATION DIVISION
Wichita, Kansas

Harry Mann
Applicant or Acting Agent

Date February 27, 1953

3-20-53

15-089-01012-00-00

W E L L R E C O R D

LEASE NAME Beard WELL NO. 1 ELEV. _____LOCATION NE 3/4 SW
S/2 SW/4 Section 10-5S-10W, Jewell County, KansasWORK COMMENCED October 31, 1952 DRILLING COMMENCED November 2, 1952DRILLING COMPLETED November 23, 1952DRILLING CONTRACTOR J. A. Melland, 1111 North Main, Hutchinson, Kans.ROTARY DRILLING FROM 0' TO 4052'

FORMATION	FROM	TO	REMARKS
Shale	0	70	
Shale and shells	70	300	Set and cemented 8-5/8" OD casing at 190' w/ 125 sacks cement.
Shale and pyrite	300	521	
Pyrite	521	555	
Lime and shale	555	1065	
Broken lime w/ shale	1065	1240	
Shale and shells	1240	1420	Circ. for samples @ 1420' 1/2 hr.
Shale and lime	1420	1485	Circ. for samples @ 1453' 1/2 hr. Circ. for samples @ 1485' 3 1/2 hrs. Ran Johnson drill stem test w/ packer set at 1447', used 38' of anchor, open 25 minutes, slight blow in 4 minutes, recovered 5' of drilling mud, BHP-330#.
Sandy lime	1485	1515	
Broken Lime	1515	1825	
Shale	1825	2385	Circ. for samples @ 2210' 1/2 hr. Circ. for samples @ 2284' 1 hr. Circ. for samples @ 2291' 3/4 hr. Circ. for samples @ 2315' 1 hr.
Shale and lime	2385	2425	
Broken Lime	2425	2471	Circ. for samples @ 2471' 3 1/2 hrs.
Shale and lime	2471	2487	Ran Johnson drill stem test w/ packer set at 2487', recovered 62' of drilling mud.
Shale and lime	2487	2540	Circ. for samples @ 2534' 1 hr.
Lime and shale	2540	2634	Circ. for samples @ 2580' 3 1/2 hrs. Circ. for samples @ 2634' 1/2 hr.
Lime	2634	2760	
Lime and shale	2760	2820	Circ. to clean hole @ 2820' 3/4 hr.
Lime	2820	2875	
Lime and shale streaks	2875	2940	Circ. for samples @ 2915' 1 hr.
Lime	2940	3190	Circ. to clean hole @ 3004' 1/2 hr.
Lime and shale	3190	3260	Ran Schlumberger Survey from 3250'. Ran Johnson drill stem test w/ double packer, top packer set at 2546' and bottom packer set at 2579', used 33' of anchor, open 15 minutes, recovered 60' of drilling mud.
Shale	3260	3345	
Shale, sandy lime & chert	3345	3400	
Chert, sandy lime & shale	3400	3415	
Cherty lime	3415	3428	
Lime and chert	3428	3472	
Lime	3472	3520	
Lime and chert	3520	3545	
Lime and shale streaks	3545	3575	
Lime, shale, iron & chert	3575	3627	
Cherty lime and shale	3627	3675	
Lime	3675	3683	
Lime and shale	3683	3705	Circ. to clean hole @ 3688' 1/2 hr.
Lime	3705	3750	Circ. for samples @ 3750' 1 hr.
Lime w/ chert streaks	3750	3790	Circ. for samples @ 3763' 1 1/2 hrs.
Lime	3790	3820	Circ. for samples @ 3793' 1 hr. Circ. for samples @ 3820' 1 hr.
Lime w/ chert streaks	3820	3928	
Lime and shale	3928	4015	Circ. for samples @ 4015' 1 1/2 hrs.
Lime and chert streaks	4015	4052	Circ. for samples @ 4023' 1 1/2 hrs.

PLUGGING

ALL SEC 10 T 5 R 10W
BOOK PAGE 62 LINE 16

FORMATION	FROM	TO	REMARKS
TOTAL DEPTH	4052		As no oil or gas was encountered in commercial quantities, authority was granted to plug the well under directions of a State Corporation Commission plugging supervisor as follows: Heavy mud from 4052' to 190', plug set at 190', 15 sacks of cement on plug, heavy mud to 40', plug set at 40', 10 sacks of cement on plug, surface soil to top. Plugged and abandoned November 23, 1952. Slope tests taken at regular intervals showed no deflections from the vertical.

C E R T I F I C A T E

I, J. A. Melland, hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

J. A. Melland
J. A. Melland

Subscribed and sworn to before me, a Notary Public, this 16th day of March, 1953.

Seward S. Greider
Notary Public

My Commission expires 1-31-57

RECEIVED
STATE CORPORATION COMMISSION
MAY 16 1953
CONSERVATION



15-089-01012-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

November 29, 1952

Well No. 1
Lease Beard
Description NE SW 10-5-10W
County Jewell
File No. 62-16

Harry Mann
Coker City
Kansas

Dear Sir:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Ruel Durkee, Box 597, McPherson, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR

F