

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-147-00684-00-00

WELL PLUGGING APPLICATION FORM

Well Location SW SW SE Sec. 9 Twp. 5S Rge. (E) 17(W)

Field Name (if any) Wildcat County Phillips

Lease (Farm Name) Wheaton Well No. No. 1

Was well log filed with application? Yes If not, explain circumstances and give available data (Use an additional sheet if necessary)

Date and hour plugging is desired to begin _____

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired (Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner _____

W. B. Faught Address Natoma, Kansas

Name of well owner or Acting Agent Harbar Drlg. - Jayhawk Oil Co.


Address 201 W-K-H Bldg., Wichita, Kansas

Invoice covering assessment for plugging this well should be sent to:

Jayhawk Oil Co. Address 201 W-K-H Bldg., Wichita, Kansas

and payment will be guaranteed by applicant.

PLUGGING
FILE NO. 9-5-17W
BOOK PAGE 86 LINE 41



John M. Little
Operator or Acting Agent

Date August 9, 1943 10-21-43

15-147-00684-00-00

HARRIS DRILLING CO. & JAYHAWK OIL CO.

Well No. 2
 SW SW SW Sec. 9, Twp. 5 S., Rge. 17 W.
 Phillips County, Kansas

Drilling Records:
 10 3/4" cemented to 192' with 100 sacks
 5 1/2" cemented to 3225' with 150 sacks

Commenced: July 12, 1943
 Completed: July 19, 1943

Elevation 1906

Log		Top	
White Rock	0 - 115	Anhydrite	1380
Shale	115 - 125	Fort Riley	1960
Shale & Shells	125 - 640	Hova	2350
Shale	640 - 705	Topoka	2875
Shale & Shells	705 - 730	Lansing	3095
Shale	730 - 1130	Comglomerate	3497
Shale & Sand	1130 - 1380	Simpson	3515
Anhydrite	1380 - 1405	Arbuckle	3562
Shale & Red Beds	1405 - 1455		
Shale & Shells	1455 - 1600	Total Depth	3610
Shale & Red Bed	1600 - 1630		
Shale & Shells	1630 - 2300		
Line	2300 - 2320		
Shale & Line	2320 - 2820		
Shale & Shells	2820 - 2890		
Line & Shale	2890 - 3010		
Line	3010 - 3355		
Line & Shale	3355 - 3389		
Shale & Shells	3389 - 3440		
Shale & Line	3440 - 3497		
Comglomerate	3497 - 3515		
Shale	3515 - 3562		
Dolomite	3562 - 3610		

Core 322A - 27 recover 6" porous line showing oil

I hereby certify that this log is true and correct to the best of my knowledge and belief.

THE TICKETS PETROLEUM CO., INC.
 By A. S. Bunte
 A. S. Bunte

Subscribed and sworn to before
 me this 15th day of June, 1943.
Arthur J. Fisher
 Notary Public

By commission expires: Oct. 24, 1944.

9 5 17W
 26 41

HARBAR DRILLING CO. & JAYHAWK OIL CO.

Wheaton No. 1
SW SW SE Sec. 9, Twp. 53., Rge 17W.
Phillips County, Kansas

Commenced: July 12, 1943
Completed: September 11, 1943 Elevation 1906

Supplementary Log

Ran Schlumberger Survey before cementing 5 1/2" casing
Top cement 3285
36 Perforations 3219 - 3229 Light show oil
1000 gal. acid by Dowell, Swab 80' fluid every 30 minutes
Stood 11 hours, fill up 180' water and 20' oil
Swab 1 1/2 hourly tests, average fill up 80' water and 5' oil each hour
36 Perforations 3219 - 3229
1000 gal. acid + 2000 gal. acid by Dowell
Swab 1/2 hourly tests, 18 hours, average fill up 60' water and 12' oil
each 30 minutes
Rip casing 3219 - 3229, fill up 195' water and 5' oil
Squeeze perforations and rips with 400 sacks cement
Perforated with 40 shots 3217 - 3231, fill up 75' water with some of oil

Dry and Abandoned.

I hereby certify that the above data is true and correct to the best of my knowledge and belief.

THE VICKERS PETROLEUM CO., INC.

By Clarence L. Hill
Clarence L. Hill

Subscribed and sworn to before
me this 15th day of October, 1943.

Christine Kuhn
Notary Public

My commission expires Oct. 24, 1944.

9 5 17W
86 41



15-147-00684-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

800 BITTING BUILDING
WICHITA, KANSAS

August 10, 1943

IN REPLY PLEASE
REFER TO THIS
SUBJECT

Well No. 9
Farm Wheaton
Description S $\frac{1}{2}$ NW 9-5-17W
County Phillips
File 86-41

Harbar Drilling Co.
Central Building
Wichita, 2, Kansas

Gentlemen:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

HA

By: J. P. Roberts
J. P. ROBERTS

NOTICE: Burt Stafford
Lyons, Kansas