

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25341-00-00  
Spot: N2S2NWNW Sec/Twnshp/Rge: 15-12S-18W  
850 feet from N Section Line, 660 feet from W Section Line  
Lease Name: LUECKE Well #: 15-1  
County: ELLIS Total Vertical Depth: 3825 feet

Operator License No.: 33269  
Op Name: CENTRAL OPERATING, INC.  
Address: 1600 BROADWAY, SUITE 1050  
DENVER, CO 80202

SURF Size: 8.625 feet: 206

# 12431

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2004 11:00 PM  
Plug Co. License No.: 30076 Plug Co. Name: ANDERSON, ANDY DBA A & A PRODUCTION  
Proposal Rcvd. from: DARRELL ANDERSON Company: ANDERSON, ANDY DBA A & A PR Phone: (785) 421-2768

Proposed Plugging Method: Ordered 215 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB Witness Type: NONE  
Date/Time Plugging Completed: 11/01/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 3788' w/25 sxs.  
2nd. Plug at 1495' w/25 sxs.  
3rd. Plug at 840' w/100 sxs.  
4th. Plug at 256' w/40 sxs.  
5th. Plug at 40' w/10 sxs. 8 5/8" wiper plug.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

RECEIVED  
NOV 08 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE

11-9-04

INV NO

2005060764

NOV 04 2004