

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21260-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 3-23S-22W  
4950 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: HOLMES Well #: 1  
County: HODGEMAN Total Vertical Depth: 4510 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

PROD Size: 5.5 feet: 4509 WITH 175 SX CMT  
SURF Size: 8.625 feet: 1097 WITH 425 SX CMT

\$146<sup>58</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2004 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KIM HAGEN Company: AMERICAN WARRIOR Phone: (620) 275-7461

Proposed Plugging Method: SAND OFF 50' ABOVE PERFS WITH 5 SX CMT. PLUG AT 1150' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/27/2004 2:50 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4504'. SANDED TO 4390' & 5 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1150' WITH 30 SX GEL & 100 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. WELL WAS FLOWING SMALL AMOUNT OF WATER UP 8 5/8" BEFORE PLUGGING.

Perfs:


Top	Bot	Thru	Comments
4440	4445		

RECEIVED  
NOV 08 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 11-9-04

INV NO 2005060763

FORM CP-212