

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22430-00-00
Spot: SENWSE Sec/Twnshp/Rge: 29-18S-9W
1700 feet from S Section Line, 1700 feet from E Section Line
Lease Name: BEHNKE Well #: 2-29
County: RICE Total Vertical Depth: 3340 feet

Operator License No.: 3842

SURF Size: 8.625 feet: 338

Op Name: LARSON ENGINEERING INC DBA LAR

Address: 562 WEST HIGHWAY 4
OLMITZ, KS 67564

\$108⁵⁵

Well Type: OH *per spot date* UIC Docket No:

Date/Time to Plug: 11/05/2004 10:00 AM

Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC

Proposal Rcvd. from: GALEN ROACH

Company: PETROMARK DRILLING, LLC

Phone: (316) 729-7406

Proposed Plugging Method: Fill hole with heavy mud and spot cement through drill pipe. Spot 35 sxs. cement @ 3,260', 35 sxs. cement @ 1,250', 35 sxs. cement @ 900', 35 sxs. cement @ 390', 25 sxs. cement @ 60', and fill rat hole with 15 sxs. cement.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: NONE

Date/Time Plugging Completed: 11/05/2004 11:30 AM

KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Perfs:

Filled hole with heavy mud and spotted cement through drill pipe. Spotted 35 sxs. cement @ 3,270', 35 sxs. cement @ 1,250', 35 sxs. cement @ 900', 35 sxs. cement @ 390', 25 sxs. cement @ 60', and filled rat hole with 15 sxs. cement.

RECEIVED
NOV 10 2004
KCC WICHITA

RECEIVED
KCC DISTRICT #2
NOV 5 - 2004
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY ALLIED CEMENTING. INVOICE #20179.

Plugged through: DP

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED

DATE 11-10-04
SER. NO. 2005060791