

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20713-00-00  
Spot: SWNWSE Sec/Twnshp/Rge: 30-17S-10W  
1650 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HICKEL Well #: 3  
County: ELLSWORTH Total Vertical Depth: 3335 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: RR 1 BOX 183B 7 SW 26TH AVENUE  
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 3335 100 SX CMT  
SURF Size: 8.625 feet: 258 180 SX CMT

\$ 108 39

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/22/2004 3:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Sand perms to 3260'; put 4 sxs cement on top; cut off 4-1/2" @ 2000'; pull to 1300'; pump 35 sxs; pull to 950'; pump 35 sxs;  
Plugging pull to 310'; and circ cement to surface.  
Method:

RECEIVED  
KCC DISTRICT #2

OCT 26 2004

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL WICHITA, KS  
Date/Time Plugging Completed: 10/22/2004 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3260' and put 4 sacks of cement on top. Cut off 4-1/2" casing at 2010'. Pulled to 1300' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 310' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland Cement #25118

Perfs:

Top	Bot	Thru	Comments
3310	3312		

RECEIVED  
NOV 10 2004  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 11-10-04 90  
INV. NO. 2005060790