

3 022552

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

KCC
SEM
11/10/04
Per
Footage

API NUMBER

NW,NE,NW 1/4

Sec/Twp/Rge S.11-T.26S.-R.18E.

4732 feet from south section line

2646 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

MUELLER NO. 4

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth

800' feet

Name & FEE FUND PLUGGING

Production Pipe:

Size Feet

Address

Surface Casing:

8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE,LLC

Lic. #

30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at:

Hour:

9:00A.M.

Day:

19

Month:

4

2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: W & W PRODUCTION COMPANY

Phone:

620-431-4137

Were: THIS WELL CONSISTED OF AN UNCASSED BORE TO APPROXIMATELY 800'

THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE

FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

☒

Part

TECHNICIAN

None

Operations Completed: Hour:

12:00P.M.

Day:

19

Month:

4

2004

Actual Plugging Report:

A 5" SWEDGE WAS RAN INTO THE WELL TO 250' AND

THEN REMOVED. 1" PIPE WAS RAN INTO THE WELL TO 770'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" DRIVE PIPE AT SURFACE.

THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 250

SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (THIS WELL WAS IDENTIFIED AS GPS SESSION PT. 4)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

APR 26 2004

KCC WICHITA