

15-001-01883-00-00

3 022551

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER 15-001-~~01883~~ 00-00

NW,NE,NW 1/4 Sec/Twp/Rge S.11-T.26S.-R.18E.

5134 feet from south section line

3395 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# MUELLER NO.3

Operator License #

County ALLEN

Operator: STATE OF KANSAS

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 800'

Address

Surface Casing: 6 1/4 Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐ D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE,LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:30P.M. Day: 16 Month: 4 2004

Plugging proposal received from: CLAYTON P. TITEL

Company Name: W & W PRODUCTION COMPANY Phone: 620-431-4137

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All ☒ Part ☐None ☐

Operations Completed: Hour: 2:30P.M. Day: 16 Month: 4 2004

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE

2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT

TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL

WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 900 P.S.I.. 43 SACKS OF

CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (THIS WELL WAS IDENTIFIED AS GPS SESSION PT. 1)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:



TECHNICIAN

RECEIVED

APR 26 2004

KCC WICHITA