

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20600-00-00
Spot: S2NENW Sec/Twnshp/Rge: 20-23S-34W
4520 feet from S Section Line, 3300 feet from E Section Line
Lease Name: PINEY Well #: 4
County: FINNEY Total Vertical Depth: 4950 feet

Operator License No.: 33136
Op Name: ANADARKO E & P COMPANY LP
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 4100 WITH 5 SX CMT
MSCC Size: feet: 2990 CMT TO SURFACE
PROD Size: 5.5 feet: 4949 WITH 560 SX CMT
SURF Size: 8.625 feet: 707 WITH 600 SX CMT

88
B110

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2004 3:00 PM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY ESCEBEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: SET CIBP @ 4100' WITH 5 SX CMT. RUN TUBING TO 1150' & CIRUCLATE CMT TO SURFACE. PUL TUBING & TOPP OFF WITH 50 SX CMT FOR BACKSIDE. 25 SX CMT AT 1950'.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/29/2004 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 4100' WITH 5 SX CMT ON TOP. PULL UP 100', LOAD HOLE WITH MUD. SDON. 10/29/04: PULL OUT OF HOLE WITH TUBING TO 1950'. LOAD HOLE & PUMP 25 SX CMT. DISPLACE WITH MUD. GOOD CIRCULATION. PULL OUT OF HOLE WITH TUBING TO 1150' & PUMP CMT FROM 1150' TO SURFACE. PULL OUT OF HOLE WITH TUBING & TOP OFF 5 1/2" WITH 145 SX CMT TOTAL. PUMP 10 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURE TO 500# AND SHUT IN.

Perfs:


Top	Bot	Thru	Comments
4726	4775		
4164	4170		

RECEIVED
NOV 03 2004
KCC WICHITA

Remarks: USED CLASS H CMT BY EAGLE WELL SERVICE. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Jim Holland PERT II
(TECHNICIAN)

INVOICED

DATE 11-3-04

INV. NO. 2005060740

Form NP-23