

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20052-00-00  
Spot: NW Sec/Twnshp/Rge: 11-30S-32W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: WATSON Well #: 11-1  
County: HASKELL Total Vertical Depth: 2740 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: PO BOX 18496 6200 N WESTERN AVE.  
OKLAHOMA CITY, OK 73154

PROD Size: 5.5 feet: 2739 WITH 475 SX CMT  
SURF Size: 8.625 feet: 604 WITH 250 SX CMT

89 05

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2004 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RANDY GASSOWAY Company: CHESAPEAKE OPERATING Phone: (405) 848-8000

Proposed Plugging Method: PUMP 200# & CMT ON BOTTOM. FILL 5 1/2". PRESSURE CHECK. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/27/2004 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 200# HULLS MIXED IN CMT TO PLUG BOTTOM. PUMP 5 1/2" CASING CAPACITY (APPROX. 230 SX CMT), NO PRESSURE, NOT ON VACUUM. PUMP 1 BBL DOWN 5 1/2" X 8 5/8" ANNULUS. PRESSURED TO 300 PSIG IMMEDIATELY. ANNULUS FULL. PUMP 30 SX CMT DOWN 5 1/2". PRESURE TO 500 PSIG & SHUT IN. PUMPED 260 SX CMT TOTAL IN 5 1/2" CASING.

Perfs:


Top	Bot	Thru	Comments
2684	2686		

RECEIVED  
NOV 03 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II  
(TECHNICIAN)

INVOICED

DATE 11-3-04

INSTR. NO. 2005060741