

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20190-00-01
Spot: NWNENE Sec/Twnshp/Rge: 20-21S-4E
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: REAMEY Well #: 34
County: MARION Total Vertical Depth: 3080 feet

Operator License No.: 5375
Op Name: HILLENBURG OIL CO.
Address: 11600 SOUTH LYNN LANE ROAD
BROKEN ARROW, OK 74011

CIBP Size: feet: 2440
PROD Size: 7 feet: 2584 150 SX CMT
SURF Size: 10.75 feet: 103 125 SX CMT
TI Size: 1 feet: 250 91 sx

#100¹⁰

Well Type: SWD UIC Docket No: D25001.0 Date/Time to Plug: 06/10/2004 1:00 PM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: RICHARD MORRIS Company: HILLENBURG OIL CO. Phone: (620) 628-4777

Proposed Plugging Method: C.I.B.P. sat at 2,450'. Run 2 7/8" tubing to 2,450' and spot 25 sxs. cement. Pull tubing to 250' and circulate cement to the surface.

**RECEIVED
KCC DISTRICT #2
OCT 28 2004**

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE **WICHITA, KS**
Date/Time Plugging Completed: 06/10/2004 3:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Ran 2 7/8" tubing to 2,450' and spotted 50 sxs. cement w/3% CaCl. Pulled tubing to 250' and circulated 76 sxs cement to the surface.

Perfs:

Top	Bot	Thru	Comments
2412	2417		
2376	2886		

**RECEIVED
NOV 04 2004
KCC WICHITA**

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID CO., INC. INVOICE #5547.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 11-4-04
INV. NO. 2005060755