

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-017-20864-00-00  
Spot: E2E2NW Sec/Twnshp/Rge: 16-20S-7E  
1320 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: PRETZER C Well #: 1  
County: CHASE Total Vertical Depth: 1362 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

SURF Size: 7 feet: 93 50 SX

#44<sup>27</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2004 4:00 PM  
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.  
Proposal Rcvd. from: ALAN L. DE GOOD Company: UNITED CEMENTING AND ACID C Phone: (316) 321-4680

Proposed Plugging Method: RAN DRILL PIPE TO 260'. BROKE CIRC., MIX & PUMP 70 SX, 60/40 POZ & 4% GEL TO SURF. PULLED DRILL PIPE & TOPPED OFF W/28 SX 60/40 POZ & 4% GEL TO SURF. CMT STAYED IN COLLAR.

Plugging Proposal Received By: MICHAEL WILSON  
Date/Time Plugging Completed: 06/01/2004 6:30 PM

WitnessType: NONE  
KCC Agent: MICHAEL WILSON

RECEIVED  
KCC DISTRICT #2  
OCT 28 2004  
WICHITA, KS

Actual Plugging Report:

Filled hole with heavy mud and spotted cement through drill pipe. Ran drill pipe to 260' and circulated 98 sxs. cement to the surface.

Perfs:

RECEIVED  
NOV 04 2004  
KCC WICHITA

Remarks: USED 60/40 POSMIX W/4% GEL BY UNITED CEMENTING & ACID CO., INC. INVOICE #5520.

Plugged through: DP

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 11-4-04  
INV. NO. 2005060752