

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20553-00-00
Spot: NWNW Sec/Twnshp/Rge: 33-34S-21W
4950 feet from S Section Line, 330 feet from W Section Line
Lease Name: BARBY-HARPER Well #: 1-33
County: CLARK Total Vertical Depth: 5559 feet

Operator License No.: 7744
Op Name: SHO-BAR ENERGY, INC.
Address: 215 E. 14TH
HARPER, KS 67058

COND Size: 13.38 feet: 361 WITH 350 SX CMT
PROD Size: 4.5 feet: 5558 WITH 175 SX CMT
SURF Size: 8.625 feet: 832 WITH 500 SX CMT

\$180⁶⁷

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/28/2004 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: LOAD WITH MUD. 20 SX CMT & 200# HULLS ON BOTTOM. PLUG AT 860' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2004 12:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PUMP 200# HULLS & 20 SX CMT ON BOTTOM. 1ST PLUG LOAD HOLE WITH MUD. PUMP 50 SX CMT AT 860'. 2ND PLUG PULL TO 400' & PUMP 30 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CM.T

Perfs:


Top	Bot	Thru	Comments
5440	5558		

RECEIVED
NOV 04 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 3036' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED

DATE 11.4.04
TEL. NO. 205060758