

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21298-00-00
Spot: NESW Sec/Twnshp/Rge: 22-27S-19W
1980 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BRENSING A Well #: 4
County: KIOWA Total Vertical Depth: 4885 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N, STE1010D PO BOX
WICHITA, KS 67275

PROD Size: 5.5 feet: 4887 WITH 250 SX CMT
SURF Size: 8.625 feet: 410 WITH 250 SX CMT

\$158⁷⁶

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/27/2004 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PLUG AT 1250' WITH 50 SX CMT. PLUG AT 430' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. 12 SX GEL FOR SPACER.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2004 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG PULL 5 1/2" CASING TO 1225'. PUMP 12 SX GEL & 50 SX CMT. 2ND PLUG PULL TO 440' & PUMP 50 SX CMT. 3RD PLUG AT 40-0' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4812	4816		

RECEIVED
NOV 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2748' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED
DATE 11-4-04
INV. NO. 2005060759