

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21225-00-00
Spot: W2NENE Sec/Twnshp/Rge: 27-27S-19W
4620 feet from S Section Line, 990 feet from E Section Line
Lease Name: BRENSING B Well #: 4
County: KIOWA Total Vertical Depth: 4875 feet

Operator License No.: 5118
Op Name: TGT PETROLEUM CORPORATION
Address: 7570 W 21ST ST N, STE1010D PO BOX
WICHITA, KS 67275

PROD Size: 5.5 feet: 4876 WITH 220 SX CMT
SURF Size: 8.625 feet: 416 WITH 250 SX CMT

#158 44

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/02/2004 11:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JERRY SULLIVAN Company: TGT PETROLEUM Phone: (316) 773-2266

Proposed Plugging Method: SAND TO 4680' WITH 5 SX CMT. PLUG AT 1200' WITH 5 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2004 1:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4876'. SANDED BACK TO 4740' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 1200' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 430' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4818	4822		

RECEIVED
NOV 04 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2615' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 11.4.04

INV. NO. 2005060959

Form 08-23