

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05016-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 2-11S-16W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GISH C Well #: 1
County: ELLIS Total Vertical Depth: 3549 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

CIBP Size: feet: 3124
CIBP Size: feet: 3190
CIBP Size: feet: 3320
PROD Size: 4.5 feet: 3549 175 SX
SURF Size: 8.625 feet: 249 200 SX

115 34

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (785) 483-9169

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2004 11:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Perforated at 1270' and 825'.
RIH with tubing to 1998' - pumped 75 sxs cement with 300# hulls.
Pulled tubing to 990' - pumped 40 sxs cement with 100# hulls - cement at surface.
Pulled tubing - pumped 25 sxs cement on 8 5/8". S.I.P. 200#.
Pumped 25 sxs down 4 1/2" casing.
Max. P.S.I. 800#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3216	3304		
3158	3171		
2892	2894		

RECEIVED
NOV 03 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Dennis L. Hamel
(TECHNICIAN)

INVOICED

DATE 11-3-04

NO. 7005060751

OCT 29 2004

01001

CITIG SERVICE OIL

#1

GISH C

2-11-16W
NW NW NE

Contr. _____ ELLIS _____ County

E. 2070 Comm. 12-17-48 Comp. 1-22-49 IP 205 BOPD & 73 BW
PHY POT

Tops	Depth	Datum
HEEB	3196	
LANS	3242	
T.D.	3549	

Casing

8" 249
4" 3549

PERF 22 S, 3340-48, 24 S,
3326-56, 13 S, 5216-24, SSO
& WTR: CO 3534: PERF 34 S,
3520-30: 46 S, 3430-44: 30
3404-14: 48 S, 3356-68: ACID
3000: PMP 20 90 & 409 BW/
19 HRS: 3QZPERF: PERF 47 S,
3292-3304: 46 S, 3272-85, 24
S, 3242-48, 21 S, 3216-22,
N.S.: ACID 3000: SWB 10 80 &
40 60/6 HRS: ACID 3000:
PMP 130. 80 & 45 BW/9 HRS

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS