

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 023 - 20,175-00-00 (of this well)
Lease Owner Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, KS 67202
Lease (Farm Name) SELVIDGE #1 Well No. #1
Well Location C SW NW Sec. 34 Twp. 4S Rge. 38W (E) _____ (W) 38W
County Cheyenne County Total Depth 5200' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 12:00 noon, 3/26/81

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

W. W. Towns (Toolpusher) Address Friendly Acres, Lot #12, Colby, KS 67701

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, KS 67202

Invoice covering assessment for plugging this well should be sent to RECEIVED
Abercrombie Drilling, Inc. STATE CORPORATION COMMISSION

Address 801 Union Center, Wichita, KS 67202 APR - 2 1981

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge 4-2-81
Applicant or Acting Agent.
Jack L. Partridge, Vice President

Date: April 1, 1981

KANSAS


WELL COMPLETION REPORT AND
DRILLER'S LOG

API No. 15 — 023 — 20,175 — 00-00
County Number

S. 34 T. 4S R. 38W E. W.

Loc. C SW NW

County Cheyenne County
640 Acres
N



Locate well correctly
Elev.: Gr. 3511'

DF 3514' KB 3516'

Operator
Abercrombie Drilling, Inc.

Address
801 Union Center, Wichita, KS 67202

Well No. #1 Lease Name SELVIDGE

Footage Location
1980' feet from (N) (S) line 660' feet from (E) (W) line

Principal Contractor Abercrombie Drilling, Inc. Geologist Bill Darrow

Spud Date 3/16/81 Date Completed 3/26/81 Total Depth 5200' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	20#	407'	60-40 posmix	300	2% gel, 3% c.c.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS
Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

RECEIVED
CORPORATION COMMISSION
APR - 2 1981 4-2-81
CONSERVATION DIVISION
Wichita, Kansas

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Abercrombie Drilling, Inc.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **#1** Lease Name **SELVIDGE** Dry Hole

S 34 T 4S R 38 ^E/_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & Sand	0	408	<u>SAMPLE TOPS:</u>	
Shale	408	1329		
Sand & Shale	1329	2430	Anhydrite	3251'
Shale	2430	3016	B/Anhydrite	3289'
Shale & Sand	3016	3507	Topeka	4188' (-672)
Shale	3507	3635	Heebner	4322' (-806)
Shale & Sand	3635	3850	Lansing	4378' (-862)
Lime & Shale	3850	4702	Stark Shale	4590' (-1074)
Lime	4702	4805	Marmaton	4695' (-1179)
Lime & Shale	4805	4857	Pawnee	4786' (-1270)
Lime, Shale & Sand	4857	5060	Fort Scott	4836' (-1320)
Lime	5060	5200	Cherokee	4867' (-1346)
Rotary Total Depth		5200		
DST #1 (4448'-4493') 30", 45", 30", 30". Rec. 15' Mud. IFP 71#-71#, ISIP 1269#, FFP 71#-71#, FSIP 551#.			<u>ELECTRIC LOG TOPS:</u>	
DST #2 (4764'-4805') 30", 45", 30", 30". Rec. 5' Mud with oil spots. FIP 71#-71#, ISIP 112#, FFP 91#-91#, FSIP 102#.			Anhydrite	3248' (+268)
			B/Anhydrite	3283' (+233)
			Wabaunsee	3965' (-449)
			Topeka	4187' (-671)
			Heebner	4314' (-798)
			Lansing	4374' (-858)
			Stark Shale	4588' (-1072)
			Marmaton	4694' (-1178)
			Pawnee	4782' (-1266)
			Fort Scott	4831' (-1315)
			Cherokee	4856' (-1602)
			Mississippi	5118' (-1602)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Jack L. Partridge Signature
 Jack L. Partridge
 Vice President Title

April 1, 1981 Date

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

April 21, 1981

INVOICE NUMBER: 5082-W

TO: Abercrombie Drlg., Inc.
801 Union Center
Wichita, Kansas, 67202

15-023-20175-00-00

PLUGGING ASSESSMENT AS FOLLOWS:

Selvide #1
C SW NW, Sec. 34-4S-38W
Cheyenne
Abercrombie Drlg., Inc.

PAID UPON RECEIPT

\$169.00

NOTE: We also need the following before our file is completed:


- Well Plugging Record (CP-4)
- Well Log
- Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



For Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Palco, Ks. 67657

is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE