

15-039-00011-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

Well Location NE/4 SE/4 Sec. 28 Twp. 4 Rge. 28W (E) (W)

Field Name(if any) None County Decatur

Lease (Farm Name) Fred Bremer Well No. 1

Was well log filed with application? no If not, explain circumstances and give available data (Use an additional sheet if necessary)

Will be filed with plugging report.

Date and hour plugging is desired to begin at once

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired (Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner

Victor Chancellor Address Box #774, Great Bend, Kansas

Name of well owner or Acting Agent Sinclair Prairie Oil Company

Address Box #521, Tulsa, Oklahoma

Invoice covering assessment for plugging this well should be sent to:

Victor Chancellor Address Box #774, Great Bend, Kansas

and payment will be guaranteed by applicant.



Operator or Acting Agent

Date September 29, 1944

28 4 28W
134 8

10-03-1947

Well Log
Sinclair Prairie Oil Co

15-039-00011-00-00

Fred Bremer # 1
NW/4 SE/4, 28-4S-28W, Decatur Co., Kas.
330 ft fm Nth & West lines
Elev. 2707'


Holm Drilling Co- rotary
Began drlg 9-2-1944
Comp. drlg 9-26-1944
TD 4656'

Clay-Sand & Gravel	135'	
Shale & Sand	280	
Shale sandy	300	
Shale blue (13" set at 340 ft)	1070	Run 350 ft 50# LW SH 13"
Shale & Shells	1310	set at 340' w/325 sz/
Shale dark-Lime shells	1665	
Lime & Shale	1800	
Shale & Lime	1910	
Shale dark-Lime shells	1920	
Shale Sandy	1960	
Lime & Shale	2140	
Shale red & Shells	2185	
Shale & Gyp	2340	
Shale red	2495	
Gyp & Shale	2545	
Shale	2560	
Shale-Gyp & Lime	2715	
Lime & Shale	2850	
Shale red	2910	
Lime-sandy hard	2920	
Shale & Gyp	2930	
Lime-gray hard	2955	
Lime broken	3040	
Lime & Shale	3100	
Shale red, Lime Shells	3200	
Lime broken	3220	
Lime grey hard	3270	
Lime brown hard	3285	
Lime gray hard	3320	
Limegray med.	3400	
Lime gray hard	3600	
Lime-broken	3621	
Lime gray med.	3660	
Lime-gray hard	3690	
Lime	3746	
Lime-lite hard	3815	
Lime-lite, med, hard	3929	
Chert	3930	
Chert & Lime	3945	
Lime lite hard	3976	
Lime	3977	
Lime-lite hard	4031	
Lime	4057	
Lime-lite hard	4105	
Conglomerate	4370	
Lime & Chert	4390	
Chert	4412	
Chert & Conglomerate	4424	
Chert	4426	
Lime & Chert	4500	
Lime-brown hard	4550	
Lime-gray hard	4560	
Lime-lite med.	4656 TD	

Run Schlumberger - dry hole

At TD 3976' took drill stem test as had oil show at 3960-69'
Drill stem test 3959-3977' open 45 mins, recovered 90 ft salt
water & drlg mud, slight show dark brown oil.

Plugged & abandoned 9/30/1944.





STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA 2, KANSAS

October 6, 1944

IN REPLY PLEASE
REFER TO THIS
SUBJECT

15-039-00011-00 -00

Well No. 1
Farm Fred Bremer
Description NE SE 28-4-26W
County Decatur
File 134-8

Sinclair Prairie Oil Co.
Box 774
Great Bend, Kansas

Attention: Mr. Victor Chancellor

Gentlemen:

This letter is your permit to plug
the above subject well, in accordance
with the Rules and Regulations of the
STATE CORPORATION COMMISSION.

Yours very truly,

STATE CORPORATION COMMISSION

T. A. MORGAN, DIRECTOR
CONSERVATION DIVISION

JF

By:

J. P. Roberts
J. P. ROBERTS

NOTICE:

H. W. Kerr
Great Bend, Kansas