

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1977  
07-15-1977  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 039 - 20393-00-00 (of this well)  
Lease Owner Gemini Corporation  
Address Box 818, McCook, Nebraska 69001  
Lease (Farm Name) BISHOP Well No. #2-8  
Well Location SW SE SW Sec. 8 Twp. 4 S Rge. (E) 28 (W)  
County Decatur Total Depth 4100 Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 7-10-77, 9:30 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 S. 2nd St., Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. \_\_\_\_\_

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Gemini Corporation

Address Box 818, McCook, Nebraska 69001

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge  
Applicant or Acting Agent  
Jack L. Partridge, Ass't. Sec.-Treas.  
Date: July 13, 1977

OPERATOR:  
 CONTRACTOR:  
 WELL NAME:  
 LOCATION:  
 SPUD DATE:  
 COMPLETION DATE:

Gemini Corporation  
 Abercrombie Drilling, Inc.  
 BISHOP #2-8  
 SW SE SW Section 8-4S-28W  
 Decatur County, Kansas  
 July 2, 1977  
 July 10, 1977

0	208	Surface soil, sand & shale
208	485	Shale
485	2145	Shale & sand
2145	2559	Shale
2559	2593	Anhydrite
2593	2759	Shale
2759	3501	Lime & shale
3501	3596	Shale & lime
3596	3844	Lime & shale
3844	3906	Shale & lime
3906	3965	Lime
3965	3980	Lime & shale
3980	4053	Shale & lime
4053	4100	Lime
	4100	Rotary Total Depth

Spud hole at 5:00 p.m., July 2, 1977. Drilled 208' of 12 1/4" hole, set 193.64' of used 8-5/8", 28#, steel casing set at 202.39'. Cemented with 180 sacks of 60-40 Posmix, no gel, 3% CaCl. Plug was down at 9:00 p.m., July 2, 1977.

T.D. 4100'. Set 1st plug at 1500' with 70 sacks, 2nd plug at 200' with 20 sacks and 3rd plug set at 40' with 10 sacks; Halliburton Cement. Plug was down at 9:30 a.m., July 10, 1977. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite 2559'  
 B/Anhydrite 2593'

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 15 1977  
 CONSERVATION DIVISION  
 WICHITA, KANSAS


STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Bishop #2-8, SW SE SW Section 8-4S-28W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge  
 Jack L. Partridge  
 Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 13th day of July, 1977.



My commission expires July 21, 1979.

Sandra Richman  
 Sandra Richman, Notary Public

State of Kansas



15-039-20393-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

July 13, 1977

WELL PLUGGING AUTHORITY

Well No.	2-8
Lease	Bishop
Description	SW SE SW Sec. 8-4-28W
County	Decatur
Total Depth	4100
Plugging Contractor	Abercrombie Drilling, Inc.


Gemini Corporation  
Box 818  
McCook, Nebraska 69001

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Gilbert Balthazar, P.O. Box 9, Route #1, Palco, Kansas 67657  
is hereby assigned to supervise the plugging of the above  
named well.