


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-039-00470-00-02
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Decatur County. Sec. 3 Twp. 4S Rge. 28 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner Sunray Mid-Continent Oil Company
Lease Name Lizzie Vavroch Well No. 1
Office Address P. O. Box 788, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 6 1960
Application for plugging filed August 2 1960
Application for plugging approved August 3 1960
Plugging commenced August 8 1960
Plugging completed August 10 1960
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3960 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237'	NONE
				5-1/2"	3958'	1603'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3930' found it clear
Dumped 4 sacks cement with dump bailer
Set rock bridge from 230' to 220', dumped 25 sacks cement from 220' to 140'. Mudded hole to 40'.
Set rock bridge from 40' to 30' dumped 10 sacks cement from 30' to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1960
08-17-1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. R. Nichols (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 788, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 16th. day of August, 19 60

My commission expires December 24, 1960

Notary Public.



Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
June 24, 1960

Contractor: Stickle Drilling Company
Date Commenced: June 13, 1960
Date Completed: June 21, 1960

Lissie Vavroch No. 1 Well,
SW/4 Sec. 3-145-28W
Decatur County, Kansas


15-039-00470-00-00

DRILLER'S LOG

Depth Figures Indicate Base of Formations:

Clay and shale	100
Hard Shale	183
Sand	220
Shale and shells	239
Shale	1350
Sand	1355
Shale	1500
Red Bed	1554
Red Bed, shale & sand	1805
Sand	1840
Red Bed, shale & shells	1990
Anhydrite	2030
Shale & Red Bed	2395
Anhydrite & shale	2446
Shale & anhydrite streaks	2695
Shale & shells	3160
Shale & lime	3260
Lime and shale	3765
Lime	3777
Lime & shale	3820
Lime	3960 TD

I, Fred E. Stickle, hereby certify the above to be a true and complete Driller's Log of Sunray Mid-Continent Oil Company's Lissie Vavroch No. 1 Well, SW/4 of Section 3-145-28W., Decatur County, Kansas.


Fred E. Stickle


Notary Public

My commission expires March 24, 1964

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1960
CONSERVATION DIVISION
Wichita, Kansas