


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Jewell County. Sec. 10 Twp. 5 Rge. 10 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines CSL NW/4  
Lease Owner Harry Mann  
Lease Name H. M. Beard Well No. 1  
Office Address Beloit, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Sept. 2 19 56  
Application for plugging filed Sept. 10 19 56  
Application for plugging approved Sept. 10 19 56  
Plugging commenced Sept. 13 19 56  
Plugging completed Sept. 14 19 56  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 2715 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15 1/2"	370'	370'
				12 1/2"	591'	591'
				10"	815'	815'
				8"	2537'	2537'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Start 8" Casing - fill hole w/ mud by Halliburton  
Start 10" Casing - refill hole w/ mud by Halliburton  
Start 12 1/2" Casing - refill hole w/ mud by Halliburton  
Pick up 15 1/2" Casing to 280' - build rock bridge and spot 60 sacks cement on bridge.  
Finish pulling 15 1/2" Casing - Mud hole - build rock bridge at 35'.  
Fill with cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Company tools (Louis M. Mai)  
Address P.O. Box 33, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss. Production Supt. for Mai Drilling  
Don E. Wolf (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 5<sup>th</sup> day of October, 19 56

My commission expires 8-9-58

Betty Jean Galyardt  
Notary Public.

PLUGGING  
FILE SEC. 10 T. 5 R. 10W  
BOOK PAGE 99 LI. E. 31



OCT 22 1956  
CONSERVATION DIVISION  
Wichita, Kansas

10-8-56