

15-089-00002-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Jewell

County. Sec. 12 Twp. 5 Rge. (E) 6 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. Center NW 1/4 SW 1/4

Lease Owner. Ralph C. Halbert

Lease Name. Rank

Well No. 1

Office Address. Box 202, Carmi, Illinois

Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole

Date well completed. 10-15 19 48

Application for plugging filed. 10-20 19 48

Application for plugging approved. Verbal Approval 10-14 19 48

Plugging commenced. 12 AM 10-15 19 48

Plugging completed. 8 AM 10-15 19 48

Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well. Ruel Durkee, McPherson, Kansas

Producing formation. Depth to top. Bottom. Total Depth of Well. 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City Lime	Dry	2300		8-5/8" O.D	163'	None
Miss. Lime	Dry	2949				
Arbuckle Lime	Dry	3701				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole Filled with heavy Mud 3740' to 160'

Halliburton Plug 160'

Spotted 15 Sx. Cement 160' to 113'

Heavy Mud 113' to 20'

Halliburton Plug 20'

Filled Hole & Covered Casing W/Cement 20' to Surface

(If additional description is necessary, use BACK of this sheet)

10-22-48

Correspondence regarding this well should be addressed to. Ralph C. Halbert

Address. P.O. Box 202, Carmi, Illinois

STATE OF Oklahoma, COUNTY OF Oklahoma

L. I. Young

(employee of Drilling Contractor)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

3111 Apco Tower, Oklahoma City, Okla.

(Address)

SUBSCRIBED AND SWORN to before me this 21st day of October, 19 48

My commission expires

March 13, 1949

Notary Public.

22-2625 2-48-15M

