

15-147-20358-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Phillips SEC. 9 TWP. 5S RGE. 17W E/W
Location as in quarters or footage from lines:

C SW NE

		x	

Locate Well
correctly on above
Section Platt.

Lease Owner KRM Petroleum Corporation
Lease Name Patton Well No. 1-9
Office Address 820 Guaranty Bank Bldg., 817 Seventeenth St. Denver, CO
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole 80202
Date Well Completed December 6, 1981
Application for plugging filed Verbally, December 6, 1981
Plugging commenced 11:30 p.m. December 5, 1981
Plugging completed 12:00 a.m. December 6, 1981
Reason for abandonment of well or producing formation

Dry Hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck

Producing formation N/A Depth to top N/A bottom N/A T.D. N/A

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8" 24#	202'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged with 135 sacks 50/50 Pozmix (4% gel, 3% CaCl)

Set 1st Plug @ 720' w/70 sacks
Set 2nd Plug @ 210' w/40 sacks
Set 3rd Plug @ 40' w/10 sacks
10 sacks rathole
5 sacks mousehole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oilwell Cementing, Inc.
P.O. Box 169, Great Bend, KS 67530


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
C.K. Morrison (employee of owner) or (~~owner or operator~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) C.K. Morrison
555 N. Woodlawn, Bldg. 1 - Suite 207
Wichita, (Address) KS 67208

SUBSCRIBED AND SWORN TO before me this 31 day of December 19 81

Suzanne P. Graef
Notary Public

My Commission expires: 10/26/85



STATE CORPORATION COMMISSION
1-9-82
JAN - 9 1982
CONSERVATION DIVISION
Wichita Kansas