

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.--82-3-117

API NUMBER 15-147-20,506 -00-00

LEASE NAME Hahn "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

2310 Ft. from S Section Line

2970 Ft. from E Section Line

LEASE OPERATOR A. L. Abercrombie, Inc.

SEC. 30 TWP. 5S RGE. 17 (E) (W)

ADDRESS 801 Union Center, Wichita, KS 67202

COUNTY Phillips

PHONE#(316) 262-1841 OPERATORS LICENSE NO. 5393

Date Well Completed 6-7-88

Character of Well D & A

Plugging Commenced 6-7-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-7-88

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Hays District Gilbert Scheck, State Plugger

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size 8 5/8	Put in 225	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Mud to 3510', 1st plug from 3510' to 3410' w/25 sx. Pump mud to 1350', 2nd plug from 1350' to 1250' w/25 sx. Pump mud to 800', 3rd plug from 800' to 400' w/100 sx plus 15 sx floccel. Pump mud to 300', 4th plug from 300' to 140' w/40 sx. Pump mud to 40', 5th plug from 40' to surface w/10sx cement. 10 sx. in rat hole. All cement 60/40 posmix w/6% gel.

(If additional description is necessary, use BACK of this to

Name of Plugging Contractor Abercrombie Drilling, Inc.

RECEIVED
STATE CORPORATION COMMISSION
License No. 5393

Address 801 Union Center, Wichita, KS 67202

JUN 23 1988

STATE OF Kansas COUNTY OF Sedgwick, ss.

7-23-88

Jack K. Wharton

CONSERVATION DIVISION

(Employee of Operator, Kansas (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center

Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 22nd day of June, 19 88

Jane A. Stuck
Notary Public

My Commission Expires: 12-29-90

