



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1963

8-28-63

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Marion Helberg of Empire Drilling Company has this

date requested permission to plug the following described well:

Mr. Helberg guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Williams Ranch Well No. 1

Location: CSE-NW Sec. 11 Twp. 4 Rge. (E) (W) 36

County Rawlins Total Depth 4860 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Helberg was instructed to plug the well as follows:

295'--8 5/8" Surface Pipe, cement circulated.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx cement.

"	"	280' with 1/4 Sk. hulls & 20 Sx cement.
"	"	30' with 1/2 Sk hulls & 10 Sx cement.

Very truly yours,

W. L. Nichols
Conservation Division Agent