



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1963

4-8-63

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pully of Forbes Casing Pulling Co. has this

date requested permission to plug the following described well:
Toto Gas Co.,

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Toto Gas Co.,

Complete Address: 7400 St., Zone 12, Oklahoma City, Oklahoma.

Lease Name: Robin Reuber Well No. 1

Location: CNW-NE Sec. 36 Twp. 4 Rge. (E) (W) 37

County Cheyenne Total Depth 4527 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pully was instructed to plug the well as follows:

304' 8 5/8" surface pipe cement circulated.

4471' 4 1/2" production casing, top of perforations @ 4445'.

Sand well back to 4435' and set 5 Sx cement w/dump bailer,

Pull 4 1/2" to 600', circulate heavy gel mud and displace 20 Sx

cement thru 4 1/2",. pull casing to 300' and displace 20 Sx cement
thru 4 1/2". Pull casing, set bridge @ 30' and 10 Sx cement to
bottom of cellar.

Very truly yours,

K. L. Nichols
Conservation Division Agent