



15-023-20007-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 9 1973
4-9-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Carter Farms Well No. A-1

Location: CSE-NW Sec. 36 Twp. 4 Rge. (E)(W) 37

County: Cheyenne Total Depth 4765' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

330'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 2000'.

Circulate hole with heavy mud. Pull DP to 2225' and displace 110 Cu. Ft. cement thru DP. Pull DP to 340' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. Cement to bottom of cellar.

Very truly yours,

Conservation Division Agent