



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1972
CONSERVATION DIVISION
Wichita, Kansas

15-039-20227-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C-G Drilling Company has this
date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C-G Drilling Company.

Complete Address: 1107 Union National Building, Wichita, Kansas.

Lease Name: Bishop Well No. 3

Location: NE-NW-SW Sec. 8 Twp. 4 Rge. (E)(W) 28

County: Decatur Total Depth 4130' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

27 1/2" -- 8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

N. L. Nichols
Conservation Division Agent