



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1972  
06-26-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-039-20122-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 1107 Union National Bank Bldg., Wichita, Kansas.

Lease Name: Bishop Well No. 2

Location: NE-SW-SW Sec. 8 Twp. 4 Rge. (E)(W) 28

County: Decatur Total Depth 4130' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

244'--8 5/8" Surface casing, cement circulated with 200 Sx.  
4129'--5 1/2" Production casing cemented on bottom with 150 Sx. Top of perforations @ 3921'.

Sand well back to 3900', set 5 Sx. cement with dump bailer @ 3900'. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 40 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Nichols  
Conservation Division Agent