



15-029-20006-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

April 22, 1976

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAY 04 1976
5-4-76
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Walter Riggs of Anadarko Production Co. has this

date requested permission to plug the following described well:

Mr. Riggs guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co. Diamond Shamrock Corp.

Complete Address: Box 351, Liberal, Kansas 67901

Lease Name: Lambert "A" Well No. 1

Location: C NE SW Sec. 22 Twp. 5 Rge. 1 XX (E) (W) X

County: Cloud Total Depth 3046' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Riggs was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks

cement through drill pipe at 500'. Pump 25 sacks cement

through drill pipe at 275'. Push plug and 1/2 sack hulls to

40' and cap hole with 10 sacks cement. Bridge rathole and

cement with 2 sacks cement. Cement mousehole with 2 sacks

cement.

Very truly yours,

William J. Roman
Conservation Division Agent