



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-039-20654-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 5 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this

date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 1107 Union National Building, Wichita, Kansas.

Lease Name: Fringer Well No. 3

Location: SE-NW-SE Sec. 8 Twp. 4 Rge. (E)(W) 28

County: Decatur Total Depth 4100 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

2 1/4' -- 8 5/8" Surface pipe, cement circulated with 190 Sx.

Circulate hole with heavy mud. Pull DP to 1680' and displace 100 Sx.

cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.

Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent