

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1967

10-23-1967

CONSERVATION DIVISION  
Wichita, Kansas

15-039-20025-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Lowell Moore of C & G Drilling Company has this date requested permission to plug the following described well:

Mr. Moore guarantees payment of the plugging fee.

Operator's full Name: C & G Drilling Company,

Complete Address: 107 Rule Building, Wichita, Kansas.

Lease Name: Bishop Well No. 1

Location: NE-SE-SW Sec. 8 Twp. 4 Rge. (E)(W) 28

County Decatur Total Depth 4160 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

243'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Dakota section from 1600' to 1460'.

Circulate hole with heavy mud. Pull DP to 1620' and displace 100 Sx.  
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

Very truly yours,

*M. L. Nichols*

Conservation Division Agent