

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

15-039-20080-00-00

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 20 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. John Kohlrus of Sage Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Kohlrus guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Incorporated,

Complete Address: 400 North Woodlawn, Wichita, Kansas.

Lease Name: PaWlicek Well No. 1

Location: NW-NW-SW Sec. 2 Twp. 4 Rge. (E)(W) 28

County: Decatur Total Depth 3975' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kohlrus was instructed to plug the well as follows:

252'---8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1400'.

Circulate hole with heavy mud. Pull DP to 1620' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. S. Nichols
 Conservation Division Agent