

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19502-00-00  
Spot: NESESE Sec/Twnshp/Rge: 11-26S-4E  
1120 feet from S Section Line, 200 feet from E Section Line  
Lease Name: HAMILTON A Well #: 18  
County: BUTLER Total Vertical Depth: 2370 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

COND Size: 10 feet: 400 MUDDER IN  
PROD Size: 6.25 feet: 2359 MUDDER IN  
SURF Size: 8.25 feet: 2043 MUDDER IN

03  
\$ 77<sup>00</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/12/2004 8:00 AM  
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: DOUG LOUIS-DISTRICT #2- RUN TUBING TO 2300', SPOT 35 SX CLASS A 3% CC, PLUG. PULL OUT. WIRELINE TAG IT, WELDER ORANGE PEELED 8-1/4 TO 6-1/4 WELD 5-1/2 COLLAR ON TOP. PERFS @ 250'. TIE ONTO 6-1/4" CIRCULATE 65/35 POZ MIX, 4% GEL CMT. REFILL 6-1/4 IF NEEDED. JUNK METAL IN HOLE @ 2302'.

RECEIVED  
KCC DISTRICT #2

Plugging Proposal Received By: DOUG LOUIS Witness Type: NONE  
Date/Time Plugging Completed: 05/12/2004 5:00 PM KCC Agent: DONALD HOBERECHT **WICHITA, KS**

OCT 20 2004

Actual Plugging Report:

Spotted 35 sacks of common cement with 3% cc at 2300' through tubing. Pulled tubing. Welded 8-1/4" to 6-1/4" with 5-1/2" collar on top. Perforated at 250' and circulated cement to surface.

United Cementing #5343, #5344 & #5497

Perfs:

Top	Bot	Thru	Comments
2359	2366		

RECEIVED  
OCT 29 2004  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE 10.29.04  
INV. NO. 2005060730