

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20641-00-00
Spot: NW Sec/Twnshp/Rge: 27-25S-8W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease Name: RICHARDSON Well #: 1
County: RENO Total Vertical Depth: 3810 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 4.5 feet: 3809 150 SX CMT
SURF Size: 8.625 feet: 253 225 SX CMT

\$ 123⁸³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/08/2004 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM, INC. Phone: (316) 245-1225

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
OCT 21 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: NONE
Date/Time Plugging Completed: 10/08/2004 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Spotted 35 sacks of cement at 1300'; 35 sacks of cement with 150 lbs cotton hulls at 700'; and circulated cement from 300' to surface with 145 sacks of cement.

60/40 posmix with 4% gel.

Copeland Acid and Cementing

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3780 | 3786 | | |

RECEIVED
OCT 29 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED
DATE 10-29-04
TEL NO 2005060722