

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-04574-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 5-20S-10W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: DREWS HENRY Well #: 5  
County: RICE Total Vertical Depth: 3391 feet

Operator License No.: 30380  
Op Name: HUPFER OPERATING, INC.  
Address: PO BOX 216  
HAYS, KS 67601

CIBP Size: feet: 3062  
PROD Size: 7 feet: 3324 175 SX CMT  
SURF Size: 10 feet: 202 175 SX CMT

\$110<sup>21</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2004 10:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DENNIS D HUPFER Company: HUPFER OPERATING, INC. Phone: (785) 628-8666

Proposed Plugging Method: CIBP @ 3062'; 3062' & 40 sxs; 1300' & 40 sxs; 900' & 40 sxs; and 409' to 0'.

RECEIVED  
KCC DISTRICT #2  
OCT 19 2004  
WICHITA, KS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/05/2004 1:30 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 3068'. Perforated casing at 1300', 900', and 409'. Ran tubing to bottom and pumped 40 sacks of cement. Pulled to 1300' and pumped 40 sacks of cement. Pulled to 900' and pumped 40 sacks of cement. Pulled to 409' and circulated cement to surface.

60/40 posmix with 4% gel.

Copeland #25071

Perfs:

Top	Bot	Thru	Comments
3032	3048		

RECEIVED  
OCT 29 2004  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Jack Luthi  
(TECHNICIAN)

INVOICED  
DATE 10.29.04  
INV. NO. 2005060724