

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-127-20576-00-00
Spot: NENESE Sec/Twnshp/Rge: 2-16S-7E
2310 feet from S Section Line, 330 feet from E Section Line
Lease Name: PICOLET Well #: 1
County: MORRIS Total Vertical Depth: 1872 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 221 S. BROADWAY
WICHITA, KS 67202

SURF Size: 8.625 feet: 178

\$ 60⁸⁴

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/13/2004 12:00 PM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: DAN Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed 1850' & 35 sxs
Plugging 200' & 35 sxs
Method: 60' & 25 sxs

RECEIVED
KCC DISTRICT #2
OCT 21 2004
WICHITA, KS

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE
Date/Time Plugging Completed: 10/13/2004 1:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The drill pipe was run open end to 1850' and spotted 35 sacks of cement (top of Arb.). Pulled pipe to 200' and spotted ' 35 sacks of cement. Pulled pipe to 60' and circulated cement to 0'.

60/40 posmix with 4% gel.

Consolidated Cement #2227


RECEIVED
OCT 29 2004
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed _____



(TECHNICIAN)

INVOICED

DATE 10-29-04
2005060726