

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21441-00-00
Spot: W2NW Sec/Twnshp/Rge: 12-26S-4E
1320 feet from N Section Line, 750 feet from W Section Line
Lease Name: ENYART A Well #: 98
County: BUTLER Total Vertical Depth: 2070 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

PROD Size: 4.5 feet: 2069 200 SX CMT
RBP Size: feet: 1556
SURF Size: 8.625 feet: 258 175 SX CMT

\$6728

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2004 8:00 AM
Plug Co. License No.: 30437 Plug Co. Name: UNITED CEMENTING AND ACID CO., INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: PER KCC DISTRICT TWO, BOTTOM PLUGS SET, CIRCULATE THRU CASING LEAK AT 404'-420', CEMENT TO SURFACE-INSIDE AND OUTSIDE 4-1/2" CASING.

RECEIVED
KCC DISTRICT #2
OCT 21 2004

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 04/08/2004 5:00 PM KCC Agent: DONALD HOBERECHT

WICHITA, KS

Actual Plugging Report:

Plugged bottom with packer at 829' with 200 sacks of Class A cement. Pulled tubing and packer, ran packer to 300', and circulated cement from 400' to surface with 154 sacks of 60/40 posmix with 4% gel.

United Cement #5497

Perfs:

Top	Bot	Thru	Comments
1978	1985		
1644	1652		
1160	1242		

RECEIVED
OCT 29 2004
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED
DATE 10-29-04
INV. NO. 2005060730