

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-20431-00-01
Spot: SENW Sec/Twnshp/Rge: 22-25S-8W
3300 feet from S Section Line, 3300 feet from E Section Line
Lease Name: KUHNS *Per ce-1 entry 10/29/04* Well #: 1
County: RENO Total Vertical Depth: 4400 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

CIBP Size: feet: 4230
PROD Size: 4.5 feet: 4268 100 SX CMT
SURF Size: 8.625 feet: 175 SURFACE

\$143⁰⁰

*KCC
BEAR
10/29/04*

Well Type: SWD UIC Docket No: D23706.0 Date/Time to Plug: 10/13/2004 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8085

Proposed Plugging Method: 1300' & 35 sxs; 700' & 35 sxs; and 250' - 0'.

RECEIVED
KCC DISTRICT #2
OCT 19 2004
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2004 4:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 4200' and 4 sacks of common cement. Cut 4-1/2" casing off at 3500'. Pulled to 1300' and pumped 35 sacks of cement. Pulled to 700' and pumped 35 sacks of cement. Pulled to 250' and circulated cement to surface.

60/40 posmix with 4% gel.

Copeland

Perfs:

Top	Bot	Thru	Comments
4268	4400		

RECEIVED
OCT 29 2004
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Jack Luthi
(TECHNICIAN)

INVOICED
DATE 10-29-04
TEL NO. 2005060722