

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21269-00-00  
Spot: W2SWSE Sec/Twnshp/Rge: 33-25S-8W  
620 feet from S Section Line, 2280 feet from E Section Line  
Lease Name: TREMBLEY Well #: 1  
County: RENO Total Vertical Depth: 4290 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 155 N. MARKET, STE. 1020  
WICHITA, KS 67202

PROD Size: 5.5 feet: 4267 150 SX CMT  
SURF Size: 8.625 feet: 338 300 SX CMT

RECEIVED  
KCC DISTRICT #2

OCT 27 2004

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/25/2004 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MACE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed CIBP  
Plugging 5 sxs @ 2330'  
Method: 35 sxs @ 1300'  
35 sxs @ 800'  
338' - 0'

\$ 139.43

Plugging Proposal Received By: JACK LUTHI  
Date/Time Plugging Completed: 10/25/2004 2:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: JACK LUTHI

Actual Plugging Report:

Set CIBP at 2330' and 5 sacks of common cement. Cut off 5-1/2" casing at 2000'. Pulled to 1300' and pumped 35 sacks of cement. Pulled to 800' and pumped 35 sacks of cement. Pulled to 338' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #20277

Perfs:

Top	Bot	Thru	Comments
2378	2380		

RECEIVED  
NOV 01 2004  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED

DATE

11-1-04

INV. NO.

2005060733