

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21332-00-01  
Spot: NENE Sec/Twnshp/Rge: 5-26S-8W  
660 feet from N Section Line, 660 feet from E Section Line  
Lease Name: FOUNTAIN Well #: 1  
County: RENO Total Vertical Depth: 4650 feet

Operator License No.: 5316  
Op Name: FALCON EXPLORATION, INC.  
Address: 155 N. MARKET, STE. 1020  
WICHITA, KS 67202

PKR Size: feet: 4308  
PROD Size: 5.5 feet: 4340 150 SX CMT  
SURF Size: 8.625 feet: 332 250 SX CMT

#151<sup>13</sup>

Well Type: SWD UIC Docket No: D27029.0 Date/Time to Plug: 10/22/2004 9:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD Company: QUALITY WELL SERVICE, INC. Phone: (785) 483-1559

Proposed Sand 4260' & 5 sxs  
Plugging 1300' & 35 sxs  
Method: 800' & 35 sxs  
380' - 0'

RECEIVED  
KCC DISTRICT #2  
OCT 27 2004  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/22/2004 4:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Perfs:

Cut 5-1/2" casing off at 2840'. Pulled to 1300' and pumped 35 sacks of cement. Pulled to 800' and pumped 35 sacks of cement. Pulled to 380' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #15350

RECEIVED  
NOV 01 2004  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

*Jack Luthi*  
\_\_\_\_\_  
(TECHNICIAN)

INVOICED  
DATE 11-1-04  
INV. NO. 2005060733